ROYALTY CALCULATION

Name of Work : Improvements to Roads & drains in Krishne Gowda Layout & Nrupatunga Road in ward No 15 T.Dasarahalli

Description	Qty in Cum	Constant	Total Qty
Plain Cement Concrete 1:3:6			
Sand	58.46	0.46	26.89
Jelly	58.46	0.89	52.03
Cement Concrete M20			
Sand	122.77	0.43	52.79
Jelly	122.77	0.69	84.71
wet mix macadam			
Jelly	203.24	1.00	203.24
Bituminous macadam			
Jelly	67.75	1.41	95.53
Bituminous Concrete			
Jelly	169.93	1.40	237.90
Precast Concrete Slab 100mm			
Sand	18.00	0.459	8.26
Jelly	18.00	0.88	15.80

Sl	Items	Qty	Rate	Amount
1	Sand	87.94	138.00	12136.00
2	Jelly	689.21	126.00	86841.00
			Total	98977.00

Asst.Engineer
Dasarahalli Ward No 15

Asst.Executive Engineer
T.Dasarahalli Sub Division

Scanned by CamScanner